

Up Pipe Kit for Ford 7.3L Ford Powerstroke 1999.5-2003 Models

P/N# 1043900

PLEASE READ ALL INSTRUCTIONS BEFORE INSTALLATION

KIT CONTENTS: Please check to make sure that you have all the parts listed in this kit **before** you start the disassembly of your truck.

1403101		1403102		1403103
Collector Adapter		Up Pipe (DS)		Up Pipe (PS)
Qty: 1			Qty: 1	Qty: 1
1403106	1900014		1900013	1831328C1
Bolt M8x 20mm	Nut Flange	M8	Bolt M8x 60mm	n Gasket
Qty: 4	Qty: 4		Qty: 4	Qty: 2

Required Tools

- 10mm/12mm socket & socket Wrench
- 7/16" deep socket
- Pry Bar
- Removal
 - VEH INS

VEHICLE SHOULD BE SAFELY SECURED BEFORE INSTALLATION.

- 1. Block wheels to secure vehicle.
- 2. Remove the intake hose and the top of the air box using a flat head screwdriver to loosen the clamps.



Screwdriver (flat head)

Torque Wrench



 Remove the clamp holding the downpipe to the turbine housing. (7/16" deep socket)



- 4. Remove the lower bolts for the OEM turbo feed pipes on both the exhaust manifolds from under the vehicle using a 10mm wrench and 13mm socket.
- 5. Disconnect the DS pipe from the collector. (10mm socket)
- 6. Loosen and remove the flange clamp holding the collector to the turbine on the turbo. (7/16" deep socket)
- 7. Remove the collector & PS up pipe assembly from the vehicle.

Installation



NOTE:

Leave loose to allow movement.



 Maneuver the pipe assembly into the vehicle and insert the pin on the collector casting into the turbine housing of the turbo. Install the flange clamp (7/16" socket); tighten enough to allow a bit of movement.



10. Connect the passenger side up pipe to the passenger side exhaust manifold using the supplied hardware. (1900013 & 1900014)



11. Connect the driver's side up pipe to the collector using the supplied gasket and hardware. Then connect the lower connection to the driver's side exhaust manifold with the last two 60mm bolts and nuts (10mm & 12mm).



12. Once both pipes are positioned, fully tighten the collector to turbine flange clamp then tighten all pipe connections to 22 ft/lbs.

13. Reinstall the clamp holding the downpipe to the turbine housing. (7/16" Deep Socket)



14. To complete this installation; reinstall the top of the air box and reconnect the intake hose.



If you have any technical difficulties, concerns, comments, or complaints, please phone our Technical Support hotline at (800) 887-5030 between 8:30am-5:00pm PST (Pacific Standard Time) Monday to Friday, or post a message on the BD Discussion Forums located at:

http://forum.bd-power.com/

